



## M/V Seatruck Progress

<b>General:</b>	The vessel was built for Seatruck ferries by Flensburger Schiffbau-Gesellschaft. In total a series of four vessels were delivered in 2011-2012.	
<b>Main Particulars:</b>	Length o.a.	142.00 m
	Length p.p.	133.46 m
	Breadth moulded	25.00 m
	Depth to top deck	21.35 m
	Draught (design)	5.20 m
	Deadweight	5255 t
<b>Capacity:</b>	Number of passengers	12 pers.
	Lane meters	2166 m
	Number of trucks	151 pcs
<b>Speed:</b>	Max.	21 kn
	Service (90 % MCR)	20 kn
<b>Propulsion:</b>	Diesel	
	Main engines	2 x MAN 7L 48/60 CR
	Installed power	16000 kW
	Aux. power	2 x 840 kW
	Bow thrusters	2 x 1000 kW
<b>Miscellaneous:</b>	Classification	Det Norske Veritas
	Number of vessels built	4
	IMO number (Seatruck Progress)	9506203
	IMO number (Seatruck Power)	9506215
	IMO number (Stena Performer)	9506227
	IMO number (Stena Precision)	9506239
<b>Scope of Work:</b>	Plan approval on behalf of the Owner	
<b>Ref. No.:</b>	KEH 08065	